

Abstract of Estimated Cost of IVDMC Shelter

S. No	Description	Quantity	Units	Unit Rate (PKR)	Amount	Remarks
1	Excavation (soft to medium soil) for Foundation of Community Hall & Store room , sanitation facility Septic tank, soakage pit, water trough including boundary wall foundation & Excavation of trenches for laying of Poly pipe watering.	2118.800703	Cft			
2	Backfilling (Excavated materials) backfilling in 6" thick each layer available excavated material at site.	1030	Cft			
3	Providing and laying Earthfilling with proper compaction.	1501.428125	Cft			
4	Providing and laying River sand filling with proper compaction.	646.1875	Cft			
5	Plain cement concrete (1:3:6) ration including preperation, placing/pouring. (SRC Cement, Crush angular 1/2" & sand Bolari)	143.1875	Cft			
6	Providing, laying, watering and ramming bricks ballast 1.5" to 2" gauge mixed with 25% sand .	224.001875	Cft			
7	Plain cement concrete (1:2:4) ration including preperation, placing/pouring finishing & curing. (SRC Cement, Crush angular 1/2" & sand Bolari) SRC cement used in Sub Structure and OPC used in Super structure.	292.219375	Cft			
8	Reinforec Cement Concrete (RCC 1:2:4) .(4# steel 40 grade & for rings 2# steel) including cutting ,bending binding with wire and lying in position, preperation, placing/pouring finishing & curing. (SRC Cement, Crush angular 1/2" & sand Bolari) Plinth Beam SRC cement and Lintel Beam OPC cement.	106.156375	Cft			

9	Brick Masonry First class brick work in foundation, super structure with C/M 1:4 up to 12' height using well burnt first quality brick including laying, scaffolding, curing, cleaning of site.(SRC Cement in Sub structure and OPC in Super structure & sand Bolari) (Dam Dama Bricks killen)	2066.894688	Cft			
10	1/2" thick cement plaster with 1:4 cm up to 12'-height. Interioir and exterior side of walls & exterior side of walls 6" below in ground level. Including preperation, laying, finishing and curing.(SRC Cement in Sub structure and OPC in Super structure & sand Bolari)	4868.7625	Sft			
11	1/4" thick Concrete chips (cemnt + fine crush).Including preperation, laying, finishing and curing.(SRC Cement & sand Bolari)	36	Sft			
12	Providing and applying 2 coats of distemper to interanl new plaster surface, Including preperation of surface, sand papering, fillings and one coat of primer.Nelson, kansai or Nipon , white colour.)	1684.4975	Sft			
13	Providing and applying 2 coats of weather shield to external new plaster surface, Including preperation of surface, sand papering, fillings and one coat of primer. (Nelson, kansai or Nipon , ashwhite colour.)	2262	Sft			
14	Providing and applying 2 coats of oil paint to doors, windows, Hand railing, Girdes, t-irons etc, Including preperation of surface, sand papering, fillings and one coat of primer. (Nelson, kansai or Nipon , ashwhite colour.)	566.5	Sft			

15	Steel Girder 1/4" thick (4"x7") 1rft= 4kg, for community hall, store room and sanitation facility. Length of every girder is mention in drwaing and measurement sheet. Including providing and fixing and one coat of red oxide.	90.625	rft			
16	Steel T-Iron 1/4" thick (1"x1") 1rft= 1kg, for community hall, store room and sanitation facility. Length of every t-iron is mention in drwaing and measurement sheet. Including providing and fixing and one coat of red oxide.	603.25	rft			
17	1st class Bricks tiles (12"x6") for community hall, store room, sanitation facility. Include providing and laying.	1278	No's			
18	Two layers of polythene sheet for community hall, store room and sanitation facility, including providing and laying.	1373.25	Sft			
19	Two layers of Mud plaster of Community hall, store room, sanittion facility. Laying after 3 days of preperation. Wheat straw or rice straw and lime used.	638	Sft			
20	Providing and Installion of Hand railing as per given design in drawing by using 40mm dia GI pipe.	134	rft			
21	Door steel frame (Size 3.5'x6.5) 16 SWG (4.5") Providing and fixing.	2	No's			
22	window steel frame (Size 3'x4') 16 SWG (4.5") Providing and fixing. front side grill & steel net	3	No's			
23	ventilator steel frame (Size 1.5'x1.5') 16 SWG (4.5") Providing and fixing.	1	No's			
24	Steel Door (Size 3'x6.5) Angle iron fram & 18 SWG sheet ,Providing and fixing.	1	No's			
25	Steel Window (front side grill & steel net)Angle iron fram & 18 SWG sheet, Providing and fixing.	1	No's			

26	Door (Size 3.5'x6.5) (Talhi) wooden (external opening door) include internal side kundi, Providing and fixing.	2	No's			
27	Window 3'x4' (Talhi) wood include internal side kundi and handle ,Providing and fixing.	3	No's			
28	Ventilator kail wood Providing and fixing.	1	No's			
29	Lever Handle lock for Doors providing and installation.	2	No's			
30	Providing and fixing of Flip-up Grab bars 28" length, as per drawing by using 40mm dia G.I Pipe, complete in all aspects.	1	No's			
31	Providing and fixing of Grab bars 24" length , as per drawing by using 40mm dia G.I Pipe, complete in all aspects.	2	No's			
32.01	Providing and fixing of English commode (orient brand) include connection pipe, all joints to services and drains plugging and screwing as necessary to structure complete in all aspects.	1	No's			
32.02	Providing and fixing Indian commode medium size (orient brand)	1	No's			
32.03	Providing and fixing of Wash basin medium size (Orient brand)include connection pipes, PVC flexible pipe connection, bottle trape all joints to services and drains plugging and screwing as necessary to structure complete in all aspects.	1	No's			
32.04	Providing and fixing of P-Trap 4" dia for indian commode (orient brand)	1	No's			
32.05	Providing and fixing of UPVC-T (4"x2") for vent pipe installation (Jeddah or Accufit brand)	1	No's			
32.06	Providing and fixing of UPVC cowel 2" dia on vent pipe (Jeddah or Accufit brand)	1	No's			

32.07	Providing and fixing of UPVC Pipe 4" dia for drainage with steel clips and 4" length nails (10ft each length (Jeddah Brand)	100	rft			
32.08	Providing and fixing of UPVC sho bend 4" dia for roof water drain pipe (Jeddah or accufit brand)	6	No's			
32.09	Providing and fixing of UPVC socket 4" dia for dain pipe (jeddah or Accufit brand)	3	No's			
32.1	Providing and fixing of UPVC Pipe 2" dia (vent pipe 10 ft length) including stell clips and 4" length steel nails.	1	No's			
32.11	Providing and fixing of UPVC Drain strainer (4"x6") (jeddah or Accufit brand)	2	No's			
32.12	Providing and fixing of UPVC Elbow 4" dia (Jeddah or Accufit)	4	No's			
32.13	Providing, laying & fixing of PPR- Pipe 3/4" dia in (8'x8' size sanitation) complete in all respects to their entire specification, including special such as tee, elbow, bend, sockets, union, handle valve, etc. supported on wall	40	rft			
32.14	Providing and fixing of Water Tap 3/4" (Master or super asia)	1	No's			
32.15	Providing and fixing of Toilet shower (Master or super asia)	1	No's			
32.16	Providing and fixing of T-cock (Master or super asia)	2	No's			
32.17	Providing and fixing of Side pillar cock (steel) liver handle best quality Master or super asia.	1	No's			
33.01	Providing and Installing of Cost Iron Hand Pump Abyar 4# after installion paint on it.	1	No's			
33.02	Providing, laying and testing of High Density Polyethylene (HDPE)pipe 1.25" dia in excvated trenches. Complete in all respects.	500	rft			length varies as per site need.
33.03	Providing and fixing of GI Elbow 1.25" IILM.	1	No's			
33.04	Providing and fixing of UPVC Elbow 1.25"	2	No's			

33.05	Providing and fixing UPVC Tee 1.25"x1.25"x1.25"	1	No's			
33.06	Providing and fixing GI Pipe Nipple 1.25" dia ILL (6" length (one side outer threads & other side plane	4	No's			
33.07	Providing and fixing 1.25" Dia UPVC Pipe (10ft length)	50	rft			
33.08	Providing and fixing 1.25" Dia UPVC filter Pipe (6ft length)	12	rft			
33.09	Providing and fixing PVC end cap for filter pipe1.25" dia	2	No's			
33.1	Providing and fixing Polister Tissue 10 ft Length (filter jali) include plastic tread.	2	No's			
33.11	Providing and fixing GI Pipe 1.25" dia ILL 5' length (one side outer threads & other side plane)	1	No's			
33.12	Providing and fixing check valve , 1.25"dia	2	No's			
33.13	Bore holes 30ft maximum	2	No's			
34	Providing and installtion Visibility 1 marbel and 1 steel plate (2.5' x 2') Project Detail Writing on it. Complete in all respects	2	No's			
35	Site dressing , leveling and cleaning. 30ft in all side of the structure. Complete in all respects.	1	Each			
Total					0	

Terms & Conditions:

1. Tender documents can be collected from Pakistan Fisher Folk Forum Head Office Near Moraro hall opposite TCF School Ibrahim haydri Karachi Sindh Pakistan www.pff.org.pk Ph: 0092-21-35091212-13 (9:00 a.m to 5:00 pm) till Oct 02, 2017.
2. Sealed tenders should reach at Pakistan Fisher Folk Forum Near Moraro hall opposite TCF School Ibrahim haydri Karachi Sindh Pakistan www.pff.org.pk Ph: 0092-21-35091212-13 on or before 1200 hours on Oct 02, 2017 and should be clearly marked "TENDER - Not to be opened before "17:00 hrs. on Oct 02, 2017"
3. The delivery address will normally be at project office in Jati or any designated Place in Jati.
4. Tender committee reserves the right to cancel/reject any or all offers without assigning any reason.
5. Lowest price will not be the sole criteria; quality, delivery time and previous experience will also be considered.

PAKISTAN FISHERFOLK FORUM - PFF

1. Closing date and time for submission of tenders :

2. Submission of tenders

Pakistan Fisher Folk Forum Head Office Near Moraro hall opposite TCF School Ibrahim haydri Karachi Sindh Pakistan www.pff.org.pk Ph: 0092-21-35091212-13

3. Timetable for provision

To be submitted by the bidder

4. Language of offers

All tenders documents are to be submitted in English

5. Period of validity of offers

It should be stated that all bids must be valid for a minimum of 60 days from the tender submission date.

6. Currency

Pakistani Rupee

8. Terms

The prices must be inclusive of all taxes, delivery / transportation, loading / unloading, packaging and allied costs upto the point of delivery.

9. Type of contract

Supply agreement

10. Samples Required

Samples must be submitted on or before 1200 hours on October 05th 2017at Pakistan Fisher Folk Forum Head Office Near Moraro hall